



Thematic focus: Ecosystem management, Disasters and conflicts, Climate change

Mangrove forest cover fading fast

The uniquely adapted mangrove forests on the marine-terrestrial interface preserve coastline integrity by buffering wave energy from marine processes. The ecosystem services they provide and their support for coastal livelihoods worldwide are worth at least US \$1.6 billion a year. Despite their global importance, mangroves are being lost rapidly and action is urgently needed to protect them.



Why is this issue important?

Mangroves are an important bulkhead against climate change: they afford protection for coastal areas from tidal waves and cyclones and are among the most carbon-rich forests in the tropics (Cornforth et al., 2013). In the face of rising sea levels and changing climates, coastal buffering against negative impacts of wave action will become critical and will play an important role in climate change adaptation.

Distributed in the tropical and sub-tropical regions of the world (Figure 1), mangroves provide shoreline protection and an array of ecosystem services. They support nutrient and organic-matter processing, sediment control for other inshore habitats (e.g. seagrass beds and coral reefs), and a source of wood for coastal communities. As a habitat for commercially valuable marine species (Walters et al., 2008), it is estimated that almost 80% of global fish catches are directly or indirectly dependent on mangroves (Ellison et al., 2008; Sullivan, 2005). Thus, the food security for many indigenous coastal communities is closely linked to the health of mangrove ecosystems (Horwitz et al., 2012). As much as 7% of the carbon dioxide reductions required to keep atmospheric concentrations below 450 ppm could be achieved simply by protecting and restoring mangroves, salt marshes and seagrass communities (Nellemann et al., 2009). Mangroves sequester up to 25.5 million tonnes of carbon per year and contribute more than 10% of essential organic carbon to the world's oceans (Dittmar et al., 2006).




Figure 1: Global mangrove forests distribution – 2000 (Giri et al., 2011). Map redrawn by UNEP/DEWA.

[Full Size Image](#)

What are the findings?

Mangrove ecosystems, which make up less than 0.4% of the world's forests (Spalding et al., 2010), are being lost at the rate of about 1% per year (FAO, 2007); in some areas, the rate may be as high as 2 to 8% per year (Miththapala, 2008). From 20% to 35% of the world's mangrove area has been lost since 1980 (FAO, 2007). The rates of loss are highest in developing countries where mangroves

are cleared for coastal development, aquaculture, timber and fuel production (Polidoro et al., 2010). In as few as 100 years, the world's mangrove forests may become so degraded and reduced in area that they would be considered to have "functionally disappeared" (Duke et al., 2007). Figure 2 shows the areas where mangroves are already threatened in the world.



Figure 2: Proportion of Threatened (Critically Endangered, Endangered, and Vulnerable) Mangrove Species. (Polidoro et al., 2010).

[Full Size Image](#)

Importance of mangroves

(i) Storm surge protection:

Relatively small ocean waves are reduced in height from 12% to 66% over a distance of 100 metres of mangroves and 50% to 99% over 500 metres (McIvor et al., 2012). A number of factors determine the extent of wave energy reduction, including water depth, wave period, wave height, mangrove species, stand density, and trunk and root diameter (Mazda et al., 1997) (Figure 3). In southern Thailand, where 50% of mangrove forests have been lost since 1961, Thampanya et al. (2006) found that coastlines eroded by 0.01 to 0.32 square kilometre a year from 1967 to 1998. Sediment accumulation was observed only in coastlines with mangrove forests.

In the Red River Delta in Vietnam, it has been estimated that an earthen sea dyke with a rock face on the open ocean side would require repairs in about five years, whereas the same dyke would last about 50 years if the rock face were replaced by a 100-metre-wide protective mangrove belt (Macintosh and Ashton, 2004). In another project in Vietnam, the cost of planting and protecting mangroves was about US \$1.1 million, and the project saved US \$7.3 million a year in dyke maintenance. Moreover, during Typhoon Wukong in 2000, the project areas remained unharmed while neighboring provinces suffered major losses in lives, property and livelihoods. The Vietnam Red Cross estimated that some 7,750 families have benefited from mangrove rehabilitation (Reid and Swiderska, 2008).

(ii) Provisioning value:

In some cases, the provisioning benefits of mangroves may be worth even more than their coastal protection value. The 1,800 hectares of Ream National Park in Cambodia was valued at US

\$300,000 for storm protection and erosion services alone. The additional provisioning services of the park, such as breeding grounds for fish, firewood, medicinal plants and construction materials, were valued at US \$600,000 (Emerton et al., 2002). Moreover, the park's ecosystem service benefits far exceed the value of clear cutting the area for timber and shrimp ponds (Horwitz et al., 2012).





Figure 3: Factors affecting wave energy in mangroves (McIvor et al., 2012).

[Full Size Image](#)

Threats to mangroves

(i) Conversion of mangrove forests :

Increasing population in coastal areas has spurred the widespread clearing of mangroves (Polidoro et al., 2010). Over-exploitation for fuelwood and timber production has degraded about 26% of mangrove forests around the world (Valiela et al., 2001). Shrimp aquaculture has contributed to about 38% of global mangrove loss and other types of aquaculture account for approximately another 14% (Ellison, 2008; Figure 4). In India, more than 40% of the mangrove area on the western coast has been converted to agriculture and urban development (Upadhyay et al., 2002). While direct anthropogenic impacts are the biggest threat to mangrove ecosystems, changing climates probably will pose even greater risks in the future (Gilman et al., 2008).



[Full Size Image](#)

[Full Size Image](#)

Figure 4: Satellite images showing an increase of shrimp farms in the Gulf of Fonseca, Honduras. The shrimp ponds appear as blue and pink rectangles near the water line scattered across the mangrove delta in the 2011 image, a period of 24 years since 1987.

(ii) Global temperature rise:

While mangroves often show resistance and resilience in the face of disturbances, the additional stresses brought by climate change may cause sudden and irreversible losses at many sites (Huxham et al., 2010). Warmer temperatures will increase evaporation rates and salinity in the sediments on the landward fringe of a mangrove forest. This may cause a die-back of mangroves or a reduction in diversity (Huxham et al., 2010).

(iii) Rising sea levels:

The global sea level has already risen 12 to 22 centimetres over the course of the 20th century due to global warming and sea-level rise could be the greatest threat facing the future of mangroves

(Gilman et al., 2008). If local conditions restrain mangroves from adapting to rising sea levels through inland migration, they will become increasingly submerged. Even in circumstances in which inland migration could occur, there may still be negative impacts on people, since it is the seaward fringes, and not the inland margins, that provide the most valuable environmental services for fisheries and coastal protection (López-Medellín et al., 2011).

(iv) *Storms and natural disasters* :

High levels of damage may be inflicted on mangroves during storms. A massive loss of mangroves following a hurricane in Honduras led to peat collapse, which reduced recovery rates (Cahoon et al., 2003). Furthermore, mangrove ecosystems can be converted to other types of ecosystems as a consequence of storm impact. For example, mangrove forests in Everglades National Park in Florida have been converted to intertidal mud flats following the impacts of hurricanes Andrew in 1992 and Wilma in 2005 (Smith et al., 2009).

Progress in the conservation and restoration of mangroves

Since the 2004 Indian Ocean tsunami, there has been a general increase in the awareness of the importance of mangrove ecosystems; efforts to conserve, protect and restore them can be seen in Bangladesh, India, Indonesia, Myanmar, Seychelles, Sri Lanka, Pakistan, Thailand and Vietnam (Macintosh et al., 2012). The Ministries of Environment and Natural Resources of Guatemala, Honduras and Nicaragua, in collaboration with the UN Environment Programme, have embarked on sustainable mangrove management, raising awareness of the critical role mangroves play in areas that are constantly threatened by the risk of hurricanes and sea level rise (UNEP, 2012).

What are the implications for policy?

As the negative impacts of climate change, including rising sea levels, become more evident, the economic value of coastal wetlands for protection will also increase as the need for their buffering services becomes more critical (Costanza et al., 2008). While market pressures push for mangroves to be cleared for aquaculture and urbanization, coastal land managers must consider not only the value of the services that mangroves provide, but also their potential value in the future (see Box 1).



Box 1: Successful Management: The Matang Mangrove Forest Reserve

The Matang Mangrove Forest Reserve in the State of Perak, Malaysia, is arguably the best example of a sustainably managed mangrove ecosystem and demonstrates that an effective balance can exist between the harvest of natural resources and conservation (Lavieren et al., 2012). The existing management plan regulates forestry, fishing, and aquaculture activities and only non-destructive practices are permitted. Harvesting of mangrove timber for poles, firewood, and charcoal production, occurs on a 30 year rotation cycle (Chong, 2006). Selective felling is carried during year 15 and year 20 and then a final clear-felling occurs during year 30. When necessary, re-vegetation programmes are implemented two years after the final felling. The annual value of charcoal between 2000 and 2009 was estimated to be RM 27.2 million (equivalent to approx. US\$ 8.9 million) while the annual value of poles was estimated at RM 2.6 million (equivalent to approx. US\$ 847 thousand). Fisheries in the Matang Mangroves are also an important contributor to the Malaysian economy. Fish cage and cockle aquaculture are allowed, and cockle farming is estimated to have an annual market value of RM 32.45 million (equivalent to approx. US\$ 10.7 million). Most of the natural resources obtained from the forest are exported to markets in the states of Selangor, Penang, and Kedah. This case provides evidence that mangrove forests can be conserved and enjoyed while still providing reliable long-term but reasonably high economic return for local and larger communities. It shows that when well-managed, mangroves can ensure sustainable yields of products (numbers are from the Malaysian Timber Council, 2009).

[Full Size](#)

Curbing deforestation may be more effective than reforestation. In the last decade, a study in Thailand found that the cost of restoring mangroves was US \$946 per hectare, while the cost for protecting existing mangroves was only US \$189 per hectare (Ramsar Secretariat, 2001).

Framework policy and legislation established at national levels, and integrated into a broader spatial framework of coastal zone management, should cross all sectors and involve all stakeholders to prevent piecemeal loss and degradation (Lavieren et al., 2012). For example, countries such as Tanzania and Malaysia have placed all mangroves in forest reserves under state ownership. In some locations in Australia and the United States, local policies of “no net loss” have placed specific limitations on future mangrove clearance. These strategies will be effective in the long term if backed by strong political will, enforcement measures and penalties for noncompliance.

An array of market-oriented strategies have been proposed to curtail the conversion of mangrove areas to other land uses. The fact that mangrove forests are increasingly recognized as a valuable source of revenue should in theory make it easier to entice those who benefit from mangroves to make payments for the ecosystem services that they generate (Lavieren et al., 2012). Furthermore, because mangrove forests store significant amounts of carbon and are threatened by the economic allure of conversion, they could be ideal targets for carbon financing. Such initiatives and investment funds provide exciting new opportunities to better protect natural capital, benefit communities, and utilize cost-effective green technologies to address the challenges of climate change.

Acknowledgement

Written by: Braedon Cashion^a

Production and Outreach Team: Arshia Chander^a, Ashbindu Singh^{b,c}, Erick Litswa^c, Kim Giese^b, Lindsey Harriman^a, Michelle Anthony^b, Reza Hussain^b, Tejaswi Giri^b, Theuri Mwangi^c and Zinta Zommers^c.

Special thanks to Charles Davies^a, Silvia Gada^a, Andrea Salinas^a, Lucia Scodanibbio^a, Zinta Zommers^c and Pascal Peduzzi^d for their valuable inputs and Shelley Robertson^e for copy editing.

(^a UNEP/DEWA-LAC- Panama; ^b UNEP/GRID-Sioux Falls; ^c UNEP/DEWA-Nairobi; ^d UNEP/GRID-Geneva; ^e Munk School of Global Affairs, University of Toronto)

References

- Cahoon, D., Hensel, P., Rybczyk, J., McKee, K., Proffitt, E., Perez, C., 2003. Mass tree mortality leads to mangrove peat collapse at Bay Islands, Honduras after Hurricane Mitch. *J. Ecol.* 91, 1093–1105.
- Chong, V., 2006. Sustainable utilization and management of mangrove ecosystems of Malaysia. *Aquatic Ecosystem Health and Management* 9, 249-260.
- Cornforth, A., Fatoyinbo, E., Freemantle, P., Pettorelli, N., 2013. Advanced Land Observing Satellite Phased Array Type L-Band SAR (ALOS PALSAR) to Inform the Conservation of Mangroves: Sundarbans as a Case Study. *Remote Sens.* 5, 224-237.
- Costanza, R., Pérez-Maqueo, O., Martínez, M., Sutton, P., Anderson, S., Mulder, K., 2008. The value of coastal wetlands for hurricane protection. *Ambio* 37(4), 241–248.
- Dittmar, T., Hertkom, N., Kattner, G., Lara, R., 2006. Mangroves, a major source of dissolved organic carbon to the oceans. *Global Biogeochem Cycles* 20(1), DOI: 10.1029/2005GB002570.
- Duke, N., Meynecke, J., Dittmann, S., Ellison, A., Anger, K. U. Berger, Cannicci, S., Diele, K., Ewel, K., Field, C., Koedam, N., Lee, S., Marchand, C., Nordhaus, I., Dahdouh-Guebas, F., 2007. A world without mangroves. *Science* 317(5834), 41-42.
- Ellison, A., 2008. Managing mangroves with benthic biodiversity in mind: moving beyond roving banditry. *Journal of Sea Research* 59(1-2), 2–15.
- Emerton, L., Seilava, R. and Pearith, H., 2002. Bokor, Kirirom, Kep and Ream National Parks, Cambodia: Case studies of economic and development linkages, field study report, in Review of Protected Areas and their Role in the Socio-Economic Development of the Four Countries of the Lower Mekong Region, International Centre for Environmental Management, Brisbane and IUCN Regional Environmental Economics Programme, Karachi. <http://cmsdata.iucn.org/downloads/casestudy03ream.pdf> (accessed 15.08.13).
- FAO, 2007. The World's Mangroves 1980-2005, FAO Forestry Paper 153. Rome: Forest Resources Division, FAO. The Food and Agriculture Organisation of the United Nations. 77 p.
- Gilman, E., Ellison, J., Duke, N. and Field, C., 2008. Threats to mangroves from climate change and adaptation options: a review. *Aquat. Bot.* 89(2), 237–250.
- Giri, C., Ochieng, E., Tieszen, L., Zhu, Z., Singh, A., Loveland, T., Masek, J., Duke, N., 2011. Status and distribution of mangrove forests of the world using earth observation satellite data. *Global Ecol. Biogeogr.* 20(1), 154–159.
- Horwitz, P., Finlayson, M. and Weinstein, P., 2012. Healthy wetlands, healthy people: a review of wetlands and human health interactions. Ramsar Technical Report No. 6. Secretariat of the Ramsar Convention on Wetlands, Gland, Switzerland, & the World Health Organization, Geneva, Switzerland.
- Huxham, M., Kumara, M., Jayatissa, L., Krauss, K., Kairo, J., Langat, J., Mencuccini, M., Skov, M. and Kirui, B., 2010. Intra- and interspecific facilitation in mangroves may increase resilience to climate change threats. *Philosophical Transactions of the Royal Society B: Biological Sciences* 365(1549), 2127–2135.
- Lavieren, H., Spalding, M., Alongi, D., Kainuma, M., Clüsener-Godt, M., Zafar, A., 2012. Policy Brief: Securing the future of mangroves. United Nations University. Institute for Water, Environment and Health, Canada. <http://unesdoc.unesco.org/images/0021/002192/219248e.pdf> (accessed 13.08.13).
- López-Medellín, X., Ezcurra, E., González-Abraham, C., Hak, J., Santiago L., Sickman, J., 2011. Oceanographic anomalies and sea-level rise drive mangroves inland in the Pacific coast of Mexico. *Journal of Vegetation Science* 22, 143–151.
- Macintosh, D. and Ashton, E., 2004. Principles for a code of conduct for the management and sustainable use of mangrove ecosystems. The World Bank, Washington D.C..
- Macintosh, D., Mahindapala, R., Markopoulos, M. (eds), 2012. Sharing Lessons on Mangrove Restoration. Bangkok, Thailand: Mangroves for the Future and Gland, Switzerland: IUCN.
- Malaysian Timber Council, 2009. Timber Malaysia. Retrieved from: <http://www.mtc.com.my/info/images/stories/pdf/tm-vol-15-3.pdf> (accessed 13.08.13).
- Mazda, Y., Megi, M., Kogo, M., Hong, P.N., 1997. Mangrove on coastal protection from waves in the Tong King Delta, Vietnam. *Mangroves and Salt Marshes* 1(2), 127-135.
- McIvor, A., Miller, I., Spencer, T., and Spalding, M., 2012. Reduction of wind and swell waves by mangroves. Natural Coastal Protection Series: Report 1: The Nature Conservancy and Wetlands International. <http://www.wetlands.org/LinkClick.aspx?fileticket=fh56xqzHlg%3D&tabid=56> (accessed 13.08.13).
- Miththapala, S., 2008. Mangroves. Coastal Ecosystems Series Volume 2. Colombo Sri Lanka: Ecosystems and Livelihoods Group Asia IUCN 28.

Nellemann, C., Corcoran, E., Duarte, C.M., Valdés, L., DeYoung, C., Fonseca, L., Grimsditch, G. (eds), 2009. Blue carbon: a rapid response assessment. United Nations Environment Programme, GRID-Arendal.

UNEP, 2012. Proyecto Manglares. United Nations Environment Programme. <http://www.pnuma.org/manglares/> (accessed 16.08.13).

Polidoro, B., Carpenter, K., Collins, L., Duke, N., Ellison, A., et al., 2010. The Loss of Species: Mangrove Extinction Risk and Geographic Areas of Global Concern. PLoS ONE 5(4), doi:10.1371/journal.pone.0010095.

Ramsar Secretariat, 2001. Wetland Values and Functions: Climate Change Mitigation. Gland, Switzerland. http://www.ramsar.org/cda/ramsar/display/main/main.jsp?zn=ramsar&cp=1-26-253%5E22199_4000_0 (accessed 13.08.2013).

Reid, H. and Swiderska, K., 2008. Biodiversity, climate change and poverty: exploring the links. International Institute for Environment and Development. <http://pubs.iied.org/pdfs/170341IED.pdf> (accessed 13.08.13).

Smith, T., Anderson, G., Balentine, K., Tiling, G., Ward, G. and Whelan, K., 2009. Cumulative Impacts Of Hurricanes On Florida Mangrove Ecosystems: Sediment Deposition, Storm Surges And Vegetation. Wetlands, 29(1), 24-34.

Spalding, M., Kainuma, M. and Collins, L., 2010. World atlas of mangroves. Earthscan, London.

Sullivan, C., 2005. The importance of mangroves. <http://ufdc.ufl.edu/UF00093446/00028/1x> (accessed 13.08.13).

Thampanya, U., Vermaat, J., Sinsakul, S. and Panapitukkul, N., 2006. Coastal erosion and mangrove progradation of Southern Thailand. Estuar. Coast Shelf Sci. 68 (1-2), 75-85.

Upadhyay, V., Ranjan, R., Singh, J., 2002. Human-mangrove conflicts: The way out. Curr Sci India 83, 1328-1336.

Váñela, I., Bowen, J. and York, J., 2001. Mangrove forests: one of the world's threatened major tropical environments. BioScience 51(10), 807-815.

Walters, B., Rönnbäck, P., Kovacs, J., Crona, B., Hussain, S. et al., 2008. Ethnobiology, socio-economics and management of mangrove forests: a review. Aquatic Bot 89(2), 220-236.

If you no longer wish to receive this bulletin you can [unsubscribe](#) anytime. Information is regularly scanned, screened, filtered, carefully edited, and published for educational purposes. UNEP does not accept any liability or responsibility for the accuracy, completeness, or any other quality of information and data published or linked to the site. Please read our [privacy policy](#) and [disclaimer](#) for further information.